

## BATHROOM REMODEL

- ☐ ORDER PLUMBING FIXTURES
- ☐ ORDER CABINETS IF YOU ALREADY HAVE ACCURATE DIMENSIONS
- ☐ ORDER FLOOR TILE, SINK AND FAUCET
- ☐ SELECT PAINT COLOR
- ☐ SELECT COUNTERTOP SLAB AND PLACE DEPOSIT

### DEMOLITION OF THE SPACE

- ☐ PLUMBING (IF LAYOUT CHANGE)
- ☐ OUTLET BOXES
- ☐ ELECTRICAL BOXES FOR SELECTED LIGHTING
  - ☐ OVER HEAD
  - ☐ SCONCE
  - ☐ OVER/UNDER CABINET LIGHTING
  - ☐ VANITY
- ☐ WALL REPAIRS
- ☐ FLOOR REPAIRS
- ☐ IF YOU HAD LAYOUT CHANGES NOW IS THE TIME TO TAKE THOSE MEASUREMENTS FOR THE CABINETS AND PLACE THE ORDER.
- ☐ PAINT
- ☐ FLOORING
  - ☐ TIP: If you are installing LVP please note that all floor cabinets need to be installed first.
- ☐ INSTALL ALL WALL TILES
- ☐ INSTALL VANITY CABINET OR PEDESTAL SINK
- ☐ COUNTERTOP TEMPLATE (BE SURE YOU HAVE THE SINK AND FAUCETS ON SITE)
- ☐ WHILE YOU WAIT FOR COUNTERTOP
  - ☐ CABINET PULLS
  - ☐ UPPER CABINET
  - ☐ BASED BOARDS
  - ☐ INSTALL TOILET
- ☐ ONCE COUNTERTOPS ARE INSTALLED
- ☐ OUTLETS
- ☐ BACKSPLASH
- ☐ TRIMS
- ☐ SWITCHES AND SWITCH PLATES
- ☐ TOUCH UP PAINT
- ☐ CLEAN UP

*PRO TIP: If you installed tile, mop the floors with a solution of 2 parts water and 1 part white vinegar. Once the film left behind by the grout is gone mop with the appropriate cleaner for your flooring. (verify with the flooring manufacturer)*